- 1. All construction materials and workmanship shall be in accordance to the City of Savannah's latest construction specifications and details. The system shall be designed and tested per the specifications and requirements maintained by the City Engineer.
- 2. An approved water supply for fire protection, either temporary or permanent, shall be made available as soon as combustible material arrives on the site.
- 3. All water used for construction shall be metered through an approved backflow prevention device and fire hydrant meter obtained from the Conveyance and Distribution Department.
- 4. All abandoned sanitary sewer lines shall be plugged.
- 5. It will be the responsibility of the Contractor to ensure sewer lines are placed within the easements with a minimum 7'-6" available from pipe centerline to easement line.
- 6. Contact the Utilities Protection Center (811 in Georgia or 1-800-282-7411) a minimum of seventy-two (72) hours prior to digging for location of City sewer lines.
- 7. Contractor shall notify residences a minimum of 24 hours in advance of any work that may impact them, including but not limited to: parking stall impact, loss of service, driveway cuts, removal/relocation of fences and mail boxes, sidewalk impacts, etc.

SANITARY SEWER GENERAL NOTES

STANDARD CONSTRUCTION DETAILS



SCALE: N.T.S.

DATED: SEP 2013

PLATE NUMBER:

S17