



NOTES:

1. RISER COMING THRU THE FLOOR SHALL BE 12 INCHES PLUS 3 TIMES THE DIAMETER OF THE PIPE AWAY FROM NEAREST WALL. ALL UNDERGROUND PIPING WILL BE RODDED & THRUST PROTECTED. ALLOWANCES WILL BE MADE FOR THE EXPANSION OF THE CONCRETE AROUND THE RISER.
2. FOR FINAL APPROVAL, ASSEMBLY MUST BE CENTERED IN ENCLOSURE (IF APPLICABLE). UNDER NO CONDITION WILL ANY CONNECTION BE ALLOWED BETWEEN THE SERVICE METER AND A BACKFLOW PREVENTER USED FOR THE SYSTEM CONTAINMENT. BACKFLOW PREVENTER SHALL ALWAYS BE INSTALLED DOWNSTREAM OF METER.
3. IF A PRESSURE MONITOR IS TO BE INSTALLED, ADD A TEE, VALVE, FITTINGS, AND MOUNT ON SUPPLY SIDE PRIOR TO BACKFLOW PREVENTER. UNDER NO CIRCUMSTANCE SHALL TEST PORTS BE MODIFIED OR UTILIZED FOR ANY USE OTHER THAN BACKFLOW DEVICE TESTING.
4. SIAMESE CONNECTION SHALL BE INSTALLED DOWNSTREAM OF THE BACKFLOW PREVENTION DEVICE. SEE DETAIL W-12

DOUBLE DETECTOR CHECK VALVE FOR FIRE SYSTEM

CITY OF
savannah
WATER RESOURCES AND PUBLIC WORKS BUREAU

WATER RESOURCES AND PUBLIC WORKS BUREAU
Planning & Engineering

W21