



NOTES:

1. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE CITY OF SAVANNAH DEVELOPMENT GUIDELINES, TECHNICAL SPECIFICATIONS AND STANDARD DETAILS.
2. CONCRETE IN THE ROADWAY TO BE 5000PSI PER SECTION 03300, CHAPTER 3.2 AND REINFORCED WITH FIBERMESH OR STEEL PER SECTION 3300, CHAPTER 5 OF CITY TECHNICAL SPECIFICATIONS.
3. BASE COMPACTION UNDER CURB TO BE 98% (ASTM D698).
4. CONTRACTION JOINTS TO BE SAW CUT NO LATER THAN 24 HOURS AFTER THE POUR.
4. ALL NEW CONCRETE IN THE HISTORIC DISTRICT AND AS OTHERWISE SPECIFIED BY THE STREET MAINTENANCE DIRECTOR MUST BE TINTED. THE TINT SHALL BE LAMBERT CORPORATION SAVANNAH BROWN' #4658 OR EQUAL TO BE SUPPLIED BY THE CONTRACTOR.

STANDARD CONSTRUCTION DETAILS



PERVIOUS PAVER DETAIL

PLATE NUMBER:

P01D

APPROVED:

SIGNATURE ON FILE

CITY ENGINEER

SCALE: N.T.S.

DATED: JANUARY 2013