



#### NOTES:

1. EXCAVATE MINIMUM 1' FROM FINISH GRADE. BACKFILL WITH CLEAN FILL AND COMPACT TO 100% PER SECTION 02200 - EARTHWORK.
2. FORM AND POUR 6" CONCRETE PAD AS A BASE WITH 8" HEADER CURB MONOLITHIC. CONCRETE TO BE 5,000 PSI WITH FIBERMESH. ALL WORK TO CONFORM TO CITY TECHNICAL SPECIFICATION SECTION 03300 - CAST-IN-PLACE CONCRETE.
3. PLACE 6" OF DRY-PACK. DRY-PACK TO BE 1 PART PORTLAND CEMENT TO 7 PARTS GRANITE FINES. EMBED COBBLESTONES IN THE DRY-PACK UP TO THE MAXIMUM VERTICAL DIMENSION OF THE STONE THEN SWEEP AND WASH DRY-PAC INTO SURFACE TO FILL VOIDS BETWEEN STONES.

## STANDARD CONSTRUCTION DETAILS



## COBBLESTONE STREET REPLACEMENT

PLATE NUMBER:

P01E

APPROVED:

SIGNATURE ON FILE

CITY ENGINEER

SCALE: N.T.S.

DATE: January 2013